



F.No.: NESTS/CIVIL/HSCL-JHARKHAND/65/2021
E-File No. 18692

Dated: 27.12.2022

To

Zonal Manager/s,
NPCC/ HSCL/ B&R/ WAPCOS/ TCIL/MANIDCO/EPIL/MTDC.

Sub: - Provision of Grade Slab at Plinth Level reg.

Construction of Eklavya Model Residential School/EMDBS is in progress in many locations and few schools are near completion. Recently, few cases have been received regarding provisions of RCC grade slab at Plinth Level for better longevity of flooring.

In this regard, I am directed to convey in -principal approval of competent authority for provision of RCC grade slab with nominal reinforcement at plinth level subject to availability of fund and wherever it demands as a technical requirement.

Therefore, PSU may submit the proposal wherever, they feel that RCC grade slab is required in view of poor soil conditions with proper justification and financial implications. Grade Slab shall be 100 mm thick mix M20 with nominal 8 mm reinforcement and may be provided **only** in school, hostels and kitchen buildings keeping in light availability of funds, with prior approval of NESTS.

This issues with approval of the Competent Authority.

Yours sincerely,

(K. C. Meena)

Additional Commissioner, NESTS

Copy to:

1. PS to Commissioner, NESTS.
2. Guard File.